



Odisha State Museum Bhubaneswar

Corrigendum

Name of Work: Reorganization of Ivory Gallery in Odisha State Museum, Bhubaneswar.

Tender Call Notice No.1528/OSM., dated.07.09.2022.

1. Clause No.1.3.1 may please read as the bidder can be either
 - i) A Company (Private or Public, or
 - ii) A registered partnership firm, or
 - iii) An LLP Firm
 - iv) Proprietorship firm with appropriate registration certificate.

2. Revised Bill of Quantities and Price Schedule is annexed herewith for submission by the bidders.
All other terms and conditions of the tender remain unaltered.

**Sd/-
Superintendent of Museum,
Odisha, Bhubaneswar.**

Bill of Quantities and Price Schedule

Name of the Work: conceptualization, design, supply and execution of Ivory Gallery of Odisha State Museum.

Sl. No.	Description of Item	Unit	Qty.	Basic Rate	GST	Total Amount	Total Amount in words
1.	Dismantling work of partition wall to make a thorough passage between Ivory Gallery and adjacent room along with cost of dismantling of present structures inside both the rooms as per best engineering practice. Debris so collected shall be disposed at suitable area of within 500mtrs, as per direction of works in-charge.	Set					
2.	Wall Paneling with aluminum base frame of 2ft x 2ft. with 12mm thick PVC board of density 0.575kg.per Mtr ³ and lamination on visible areas. (with material and execution). PVC board of Century/Alstone make.	Sqmtr.					
3.	Installation of Showcases, Dioramas with woolen carpet of 4mm thickness and Toughened glass of suitable thickness. All display glass should be joint less for better viewing.	Sqmtr.					
4.	Providing and fixing at site new false ceiling in Gypsum plaster board on grid framework comprising of rolled galvanized metal sections consisting of the main channels (50mmX 25mm X 24SWG) to run in	Sqmtr.					

	<p>one direction at 1000mm c/c and secondary ceiling section 70mm X 23mm X 24SWG at 450mm c/c in other direction connected to main channel with GI connecting clips of 10 SWG of approved quality. The grids shall be suspended from structural slab by GI strap hangers 25mm X 5MM size @ 1000mm C/C both ways from structural slab by using soffit cleats and expandable fasteners. Gypsum plaster board of India Gypsum make 12.5 mm thick is then screwed & fixed to ceiling section, finished with jointing compound, paper tape & two coats of primer suitable for gypboard to produce smooth surfaces i/c providing frame work for light fixtures etc. as per detail drawing.</p>						
5.	<p>Electrification of Showcase, Diorama, ceiling track lighting with lights as required, wiring in complete shape (all lighting items should be of Havells /Phillips/Crompton make) and wire of Finolex /Vguard /Polycab make, MCCB to be of L & T /Havells /Anchor and Switches of Cona /Havells make.</p>	No.					
6.	<p>12mm thick HDF Wooden flooring for entire exposed floor area with Abrasion Class-rating 3 and above of Make (Action Tesa/Square Foot/Green/Armstrong).</p>	Sqmtrs.					

7.	Providing of suitable toughened glass door of 12mm thickness at the entrance of the Gallery.	Set					
8.	Creation of Royal Darbar hall diorama with 6nos. of royal chairs, Haudaa with suitable size FRP elephant model with woolen floor carpet of 4mm thick and FRP columns & Arch of suitable size.	Set					
9.	Development of content, translation, sound track recording, video shoot and editing– stitching. programming and supply installation, testing and commissioning of the content in a 43” commercial touch screen TV with all required accessories(LG/Samsung or equivalent make) complete as per brief/design/concept/model as per the direction of site in-charge. Content should be approved by OSM for final programming and integration.	Set					
10.	Reinstallation of existing 03nos. of 3ton capacity Air conditioners	Nos.					

Signature of the Agency/ Quotationer

**Sd/-
Superintendent of Museum,
Odisha, Bhubaneswar.**